FCCI® INSURANCE GROUP

SPRINKLER SYSTEM EVALUATIONS

PREPARING FOR THE INSPECTION

The following information and documentation should be gathered in preparation for the ISO representative's evaluation of the sprinkler system:

____ The main drain test results for all sprinkler systems on the property

____ A copy of the underground and overhead piping hydrostatic test certificate for all sprinkler systems on the property

____ The dry pipe trip test results for systems with dry pipe valves

____ The fire pump field performance test for systems equipped with a fire pump

____ A copy of the system design criteria in the form of sprinkler plans, hydraulic calculations, or hydraulic data plaque information

____ The name the of sprinkler contractor who installed the system, if available

____ A contact person who will provide the ISO representative access to all areas of the building - most important, to the riser room and to all sprinkler control valves

This form is only a suggested safety list, and is not intended as the rendering of legal or safety advice by any of the FCCI Insurance Group member carriers and related entities (FCCI). There is no representation, either express or implied, that the matters discussed in this form would comply with all applicable safety codes, including OSHA and other federal or state regulations or statutes. FCCI will have no liability due to the use of this form. Please consult with legal counsel or other safety consultants with regard to the specific requirements of OSHA and other federal or state regulations or statutes.