Installation Floater Checklist

- ☐ Storage areas on jobsites should be secured from vandalism, theft, and property damage.
- ☐ Install a fence around the jobsite.
- ☐ Keep your material/equipment protected from rain, snow, wind, and rising water..
- ☐ Store items off the floor (i.e. on pallets).
- ☐ Store larger quantities of your material and equipment at more than one secured area.
- ☐ Use only insured rigging companies to lift and set your material/ equipment.
- ☐ Test/inspect all equipment, slings, harnesses, wire rope, hooks, etc., prior to making a lift.
- ☐ Use outriggers and properly position lifting equipment. This is critical.
- ☐ Brace exterior walls and trusses to withstand local wind conditions.
- ☐ Keep fire extinguishers readily accessible on the jobsite. Note: have a minimum of one fire extinguisher for every 3,000 sq. ft., maximum travel distance of 75' between them, and at least one fire extinguisher on each floor of a multi-story building.
- ☐ Keep jobsite clean and well organized. Do not allow trash to accumulate.
- ☐ Properly store all combustible liquids and gases.
- ☐ Store property away from wooded areas to help prevent damage by wildfire.
- ☐ Maintain inventory records of covered property on the site described in the policy declarations.
- ☐ Request suppliers to only ship materials and equipment, as you need them.
- ☐ Use a signed contract to verify your customer’s acceptance of your work and the materials and equipment installed.
- ☐ Have procedures in place to insure prompt notification of fire department.
- ☐ Be sure fire department is familiar with the jobsite.
- ☐ Use only Underwriters Laboratories listed heaters for temporary heating.
- ☐ Be sure a fire watch is used during cutting or welding operations.